




Tappets, Matched Pair

All prices listed are current as of 02/12/21.



Removing and Fitting the Tappets

The tappets are located in the lower part of the Cylinder Barrel retained by Four 2BA screws, two screws to each plate, passing through a separating plate for each tappet.

Current prices are:

Tappets (part # 06-7820) \$400.00 a set.

2BA screws (part # 06-7560) \$5.60 each.

Separating plate (part # 06-3092) \$15.85 each.

To remove the tappets cut the safety wire for the plate retaining screws (06-7560) and remove the screws.

The tappets are machined in pairs and must be re-fitted in the same order as they were removed. **They do not interchange**

It is most important, when re-fitting the tappets: to apply a little clean oil and ensure the beveled edges are side by side facing the front of the engine. Inadvertent reversal will restrict oil drainage and also prevent lubrication.

Firmly tighten the plate retaining screws and secure with safety wire linking the two screws

The standard tappet diameter is 1.1865" to 1.1875".

The +.020 tappet (part # 06-7820/020, \$188.93) diameter is 1.2065" to 1.2075".

The clearance between the tappets and the cylinder bore is 0.0010" to 0.0015".

**[Return to Old Britts home page](#) [Our Products, Ordering](#)
[Norton Parts.....Engine, Valve Gear](#)**
